



City of Moore Oklahoma

301 N. Broadway, Moore, OK 73160 | (405) 793-5000 | www.cityofmoore.com

NOTICE TO PROCEED

DATE: March 17, 2016
TO: Silver Star Construction
PROJECT: S. Broadway
I-14-E-URG

The City of Moore has considered the budget submitted by you for the above referenced project.

You are hereby notified the budget has been accepted in the amount of \$2,592,354.14.

You are required to return an acknowledged copy of Notice to Proceed to the City of Moore.

Dated this 17th day of March 2016.

By: 
Jared Jakubowski, Grants Manager

ACCEPTANCE OF NOTICE

Receipt of the foregoing Notice to Proceed is hereby acknowledge by Steve Shaw,
this 17th day of March, 2016.

By: 

Title: president

Silver Star Construction Co., Inc.

2401 S. Broadway - Moore, Oklahoma 73160 – (405) 793-1725 / 1-800-375-1725 / Fax (405) 793-9989

Proposal For: Broadway Ave. From S 4th to S. 16th Project # I-14-E-URG

03/08/2016

City of Moore
301 N. Broadway
Moore, OK 73160
Phone# (405) -793-5020
Fax# (405) -799-1828
Attn: Jared Jakubowski

ITEM #	DESCRIPTION	QUAN	UNIT	UNIT PRICE	EXT PRICE
200-00	UNCLASSIFIED EXCAVATION (>500 CY)	2,898.000	CY	\$ 23.60	\$68,392.80
212-01	TRENCH EXCAVATION & BACKFILL	3,833.000	CY	\$ 16.20	\$62,094.60
225-00	TYPE A BASE	505.000	CY	\$ 88.50	\$44,692.50
215-08	ROCK BACKFILL	4,824.000	TON	\$ 33.85	\$163,292.40
222-03	CEMENT KILN DUST	175.000	TON	\$ 54.00	\$9,450.00
222-05	CEMENTITIOUS STABILIZED SUBGRADE	4,973.000	SY	\$ 8.35	\$41,524.55
301-28	ASPHALTIC CONCRETE TYPE A (PG 64-22) (>600 TONS)	933.000	TON	\$ 59.70	\$55,700.10
301-31	ASPHALTIC CONCRETE TYPE A (PG 70-28) (>600 TONS)	933.000	TON	\$ 62.75	\$58,545.75
301-33	ASPHALTIC CONCRETE TYPE B (PG 70-28) (>600 TONS)	2,457.000	TON	\$ 69.00	\$169,533.00
304-07	PCC PAVEMENT (8" DOWEL JOINTED) (>500 SY)	2,261.000	SY	\$ 54.85	\$124,015.85
305-04	INTEGRAL CURB (BARRIER) (8")	590.000	LF	\$ 17.55	\$10,354.50
305-01	CURB AND GUTTER (2'-8")(8" BARRIER)	861.000	LF	\$ 28.20	\$24,280.20
823-03	6" CONCRETE DRIVEWAY (HES)	87.000	SY	\$ 83.40	\$7,255.80
309-00	COLD MILLING ASPHALT PAVEMENT (1-3/4")	16,117.00 0	SY	\$ 5.10	\$82,196.70
313-00	TACK COAT	1,346.000	GAL	\$ 5.50	\$7,403.00
200-00	UNCLASSIFIED EXCAVATION FOR CHANNEL LINER	312.000	CY	\$ 25.15	\$7,846.80
403-01	CONCRETE CHANNEL LINER	442.000	SY	\$ 77.35	\$34,188.70
403-02	CONCRETE CHANNEL LINER (TRANSITION)	90.000	SY	\$ 85.95	\$7,735.50
213-01	CRUSHED ROCK FOUNDATION FOR STORM SEWER	587.000	CY	\$ 40.60	\$23,832.20
453-01	REINFORCED CONCRETE PIPE 24"	583.000	LF	\$ 68.75	\$40,081.25
453-12	REINFORCED CONCRETE PIPE 18" O-RING	291.000	LF	\$ 60.15	\$17,503.65



Silver Star Construction Co., Inc.

2401 S. Broadway - Moore, Oklahoma 73160 – (405) 793-1725 / 1-800-375-1725 / Fax (405) 793-9989

ITEM #	DESCRIPTION	QUAN	UNIT	UNIT PRICE	EXT PRICE
453-13	REINFORCED CONCRETE PIPE 24" O-RING	91.000	LF	\$ 74.10	\$6,743.10
453-14	REINFORCED CONCRETE PIPE 36" O-RING	1,887.000	LF	\$ 112.80	\$212,853.60
453-25	REINFOCED CONCRETE PIPE END SECTION (24")	1.000	EA	\$1,047.50	\$1,047.50
812-04	ASPHALT PAVEMENT REMOVAL FOR STORM SEWER INSTALL	1,325.000	SY	\$ 13.95	\$18,483.75
454-30	JUNCTION BOX (6X6)	76.400	CY	\$ 591.00	\$45,152.40
454-34	DESIGN 2-0 INLET COMPLETE IN PLACE	12.000	EA	\$2,245.00	\$26,940.00
454-66	BOX TYPE INLET (4 X 4)	2.000	EA	\$2,825.00	\$5,650.00
460-00	SETTING NEW MANHOLE RING AND COVER	13.000	EA	\$ 389.00	\$5,057.00
700-00	TRAFFIC SIGNALS	1.000	LS	\$158,406.60	\$158,406.60
729-10	REMOVE EXISTING SIGN	2.000	EA	\$ 107.00	\$ 214.00
735-00	TRAFFIC STRIPE (PLASTIC) (4 INCH WIDE)	11,411.00 0	LF	\$ 1.03	\$11,753.33
735-01	TRAFFIC STRIPE (PLASTIC) (ARROWS) (SINGLE)	8.000	EA	\$ 242.00	\$1,936.00
801-00	CONSTRUCTION STAKING (CONSTRUCTION SURVEY)	8.000	DAYS	\$1,205.00	\$9,640.00
802-00	CONSTRUCTION SIGNING AND TRAFFIC CONTROL	1.000	LSUM	\$32,968.35	\$32,968.35
809-00	MOBILIZATION- 7%	1.000	LSUM	\$169,593.26	\$169,593.26
811-04	REMOVE STORM SEWER (RCP)	111.000	LF	\$ 38.50	\$4,273.50
811-04	REMOVE STORM SEWER STRUCTURE	1.000	EA	\$5,725.00	\$5,725.00
812-01	REMOVE SIDEWALK (6')	140.000	SY	\$ 14.00	\$1,960.00
812-02	REMOVE CURB AND GUTTER	1,234.000	LF	\$ 15.50	\$19,127.00
812-04	ASPHALT PAVEMENT REMOVAL	6,747.000	SY	\$ 13.95	\$94,120.65
819-11	REMOVE AND REPLACE LIGHT POLE	5.000	EA	\$6,831.00	\$34,155.00
820-01	SAWCUT PAVEMENT	1,976.000	LF	\$ 3.25	\$6,422.00
823-00	SIDEWALK (6')	117.000	SY	\$ 39.65	\$4,639.05
824-01	TEMPORARY BASE SURFACE COURSE	16.000	TON	\$ 35.80	\$ 572.80
830-01	DETECTABLE WARNING SURFACE	240.000	SF	\$ 43.00	\$10,320.00
830-00	ADA CURB RAMP (8" THICK)	176.000	SY	\$ 53.70	\$9,451.20
840-04	SOLID SLAB SODDING	6,445.000	SY	\$ 4.30	\$27,713.50
843-05	TREES RELOCATE	8.000	EA	\$ 209.00	\$1,672.00
900-02	ROCK BAG INLET BARRIER	22.000	EA	\$ 16.10	\$ 354.20
900-03	FILTER FABRIC SILT FENCE	8,955.000	LF	\$ 1.90	\$17,014.50
900-04	SILT DIKE	110.000	LF	\$ 8.60	\$ 946.00
900-07	SEDIMENT AND EROSION CONTROL (MAINTAIN AND REMOVE)	1.000	LSUM	\$6,437.00	\$6,437.00
225-00	TYPE A BASE (TRAILS)	450.000	CY	\$ 88.50	\$39,825.00



Silver Star Construction Co., Inc.

2401 S. Broadway - Moore, Oklahoma 73160 – (405) 793-1725 / 1-800-375-1725 / Fax (405) 793-9989

ITEM #	DESCRIPTION	QUAN	UNIT	UNIT PRICE	EXT PRICE
1000-00	8' WIDE CONCRETE TRAIL (6" THICK)	84.000	SY	\$ 41.10	\$3,452.40
1000-00	12' WIDE CONCRETE TRAIL (6" THICK)	5,186.000	SY	\$ 41.10	\$213,144.60
1000-01	OVERHEAD PARK SPECIAL ENTRY SIGN	1.000	EA	\$234,535.00	\$234,535.00
1000-02	TRAIL LIGHTING	1.000	LSU	\$90,135.00	\$90,135.00
TOTAL:					\$2,592,354.14


Bid Stipulations and Conditions:

DATE of Plans: 19 January, 2016

If a contract is entered into, the contract will be executed in, and subject to interpretation and enforcement pursuant to the laws of the State of Oklahoma. The Parties further agree that although this contract is subject to enforcement in Oklahoma, the objective reasonable person standard shall apply to its interpretation.

All contract documents to be interpreted in accordance with the objective, reasonable person standard.

Thank You,



Matt Aker

